कार्यालय, प्राचार्य शासकीय श्रीमंत माधवराव सिंधिया स्नातकोत्तर महाविद्यालय, शिवपुरी (म0प्र0)
टी.व्ही. टावर के पास, फिजिकल रोड शिवपुरी – कॉलेज कोड 0501, फोन : 07492-223481 (फैक्स) 221781
Web- http://www.govtsmspgcollegeshivpuri.org E-mail leadcollegeshivpuri@yahoo.com hegpgcshi@mp.gov.in

क्रमांक– 1983 /स्था./2022 दिनांक 26/08/202

//निविदा//

कार्यालय आयुक्त उ0शि0 भोपाल द्वारा वित्तीय वर्ष 2022–23 हेतु इस महाविद्यालय के भवन के रख–रखाव हेतु रुपये 5 लाख का आवंटन क्रमांक 521/130/आउशि/निर्माण शाखा–6 भोपाल दिनांक 14.07.22 के द्वारा किया गया है। महाविद्यालय में निम्नलिखित कार्य संलग्न पी.डब्लू.डी.SOR एवं विवरण के अनुसार कराये जाना है इस हेतु संबंधित फर्म अपनी दरें 10 दिवस के अन्दर 04.09.22 को सांयकाल 5 बजे तक प्रस्तुत करें।

न्यूनतम पी.डब्लू.डी.SOR दर पर प्राप्त निविदा को समिति द्वारा कार्यादेश दिया जायेगा, पंजीकृत ठेकेदार के द्वारा निविदा प्रस्तुत की जा निविदा के साथ 50,000=00 की धरोहर राशि प्राचार्य शासकीय स्नातकोत्तर महाविद्यालय शिवपुरी के खाते में अथवा ड्राफ्ट के द्वारा प्रदान किया जाना हो अपूर्ण निविदा को स्वीकार नहीं किया जावेगा । कार्य आदेश जारी होने के 15 दिवस के अन्दर कार्य पूर्ण करना होगा ।

संलग्नः– स्पेसीफिकेशन

26/8/22

( प्रो0 महेन्द्र कुमार )
प्रभारी प्राचार्य
शा0 स्नातकोत्तर महाविद्यालय,
शिवपुरी (म0प्र0)

पृ0क्रं0 1984 /2022 शिवपुरी दिनांक 26.08.22
प्रतिलिपिः–

1– आयुक्त, उच्च शिक्षा सतपुड़ा भवन भोपाल कृपया उपरोक्त विज्ञप्ति को विभागीय बेववसाईट पर अपलोड कराने का कष्ट करें।
2– प्रभारी प्राध्यापक , महाविद्यालय बेवसाईट पर कृपया उपरोक्त विज्ञप्ति को विभागीय बेववसाईट पर अपलोड कराने का कष्ट करें।
3– महाविद्यालय सूचना पटल पर इस आशय के साथ चस्पा कि संबंधित अपनी दरें प्रदान करें।

( प्रो0 महेन्द्र कुमार )
प्रभारी प्राचार्य
शा0 स्नातकोत्तर महाविद्यालय,
शिवपुरी (म0प्र0)

26/8/22

# DETAIL AND ABSTRACT ESTIMATE FOR RENOVATION WORK AT GOVT PG COLLEGE SHIVPURI

| S. No. | SOR Ref. | Particular | Nos | L | W | D | Qty | Unit | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|
| 1 | | Steel work in built up M.S. tubular section (round, square or rectangular hollow tubes etc.) trusses/frame work etc. including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. | | | | | | | | |
| | 10.14.1 | Hot finished welded type tubes | | | | Kg/per Sqm | | | | |
| | | Trush/ Purlin and Rafter for GS Sheet | 1 | 15 | 7 | 7.25 | 761.3 | | | |
| | | Do for Cooler Shed | 1 | 3 | 2.2 | 7.25 | 47.85 | | | |
| | | MS Compound Main gate No 2 | 1 | 4.35 | 2.4 | 40 | 417.6 | | | |
| | | Do | 1 | 1.05 | 2.3 | 40 | 96.6 | | | |
| | | MS Main gate of College | 1 | 1.8 | 2.7 | 40 | 194.4 | | | |
| | | MS gate For Cooridors | 1 | 2.1 | 2.4 | 40 | 201.6 | | | |
| | | Total qty | | | | | 1719.3 | kg | 108.00 | 185684 |
| 2 | | Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. | | | | | | | | |
| | 12.1.2 | 0.80mm thick with zinc coating not less than 275gm/m² | | | | | | | | |
| | | Do for Cooler Shed | 1 | 3 | 2.2 | | 6.6 | | | |
| | | Do for Stage Shed | 1 | 15 | 7.25 | | 108.8 | | | |
| | | | | | | | 115.4 | sqm | 863.00 | 99547 |

26/8/22

Principal
Govt. P.G. College
Shivpuri (M.P.)

| | SOR Ref. | Particular | Nos | L | W | D | Qty | Unit | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|
| 3 | SOR 10.5.2 | Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x5mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer.Using flats 30x6mm for diagonal braces and central cross piece. | | | | | | | | |
| | | Rooms | 1 | 2.08 | 2.7 | | 5.616 | | | |
| | | Cemister Cell 1 | 1 | 2.95 | 2.6 | | 7.67 | | | |
| | | Library | 1 | 2.5 | 2.35 | | 5.875 | | | |
| | | Class Room | 10 | 1.95 | 1.08 | | 21.06 | | | |
| | | Total qty | | | | | 40.22 | SqM | 2474 | 99507 |
| 4 | | Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : | | | | | | | | |
| | 21.1.2.2 | For shutters of doors, windows and ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of Powder coated aluminium (minimum thickness of powder coating 50 micron) | | | | Kg/per Sqm | | | | |
| | | | 5 | 1.7 | 1.5 | 10 | 127.5 | Kg | 345 | 43988 |

26/8/22

26/08/2022
Principal
Govt. PG. College
Shivpuri (M.P.)

| .No. | SOR Ref. | Particular | Nos | L | W | D | Qty | Unit | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|---|
| 5 | 21.3.2 | Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item) :With float glass panes of 5.0 mm thickness (weight not less than 12.50 kg/sqm ) | | | | | | | | |
| | | | 5 | 1.7 | | 1.5 | 12.75 | sqm | 948.00 | 12087 |
| | | | | | | | | | | |
| 6 | 27.8 | Providing and fixing stainless steel English (Capital) and Hindi letters in standard pattern bellow type made with 1.20 mm thick stainless steel (ASI Grade- 304 ) Depth of letter shall not be less than 30mm and rate includes welding/soldering of joints polishing, buffing and fixing on the wall, plate and beam surface at any height with necessary nut and bolts/fastener wherever is required complete as per direction of Engineer-in-Charge. | | | | | | | | |
| | | College Name In Hindi | 1 | 46 | 6 | | 276 | | | |
| | | College Name In English | 1 | 48 | 6 | | 288 | | | |
| | | | | | | | 564 | per letter per cm height | 75.00 | 42300 |
| | | Total | | | | | | | | 483113 |
| | | Add GST 18% | | | | | | | | 86960 |
| | | Grand Total | | | | | | | | 570073 |

26/8/22

26/08/2022

Principal
Govt. P.G. College
Shivpuri (M.P.)