कार्यालय, प्राचार्य शासकीय श्रीमंत माधवराव सिंधिया स्नातकोत्तर महाविद्यालय, शिवपुरी (म0प्र0)
टी.व्ही. टावर के पास, फिजिकल रोड शिवपुरी – कॉलेज कोड 0501, फोन : 07492-223481 (फैक्स) 221781
Web- http://www.govtsmspgcollegeshivpuri.org E-mail leadcollegeshivpuri@yahoo.com hegpgcshi@mp.gov.in

क्रमांक– 1999 /स्था./2022 दिनांक 29/08/2022

//संशोधित निविदा दिनांक 26.08.22//

इस कार्यालय के पत्र क्रं0 1983 दिनांक 26.08.22 के द्वारा निविदा जारी की गई थी जो संशोधित कर वेवसाईड पर प्रकाशन हेतु प्रेषित है।

कार्यालय आयुक्त उ0शि0 भोपाल द्वारा वित्तीय वर्ष 2022–23 हेतु इस महाविद्यालय के भवन के रख–रखाव हेतु रुपये 5 लाख का आवंटन पत्र क्रमांक 521/130/आउशि/निर्माण शाखा–6 भोपाल दिनांक 14.07.22 के द्वारा किया गया है। महाविद्यालय में निम्नलिखित कार्य संलग्न पी.डब्लू.डी.SOR दर एवं विवरण के अनुसार कराये जाना है इस हेतु संबंधित फर्म संलग्न **Price Schedule** पर अपनी दरें 10 दिवस के अन्दर 08.09.22 को सांयकाल 5 बजे तक प्रस्तुत करें।

न्यूनतम पी.डब्लू.डी.SOR दर पर प्राप्त निविदा को समिति द्वारा कार्यादेश दिया जायेगा, पंजीकृत ठेकेदार के द्वारा निविदा प्रस्तुत की जावे निविदा के साथ 50,000=00 की धरोहर राशि प्राचार्य शासकीय स्नातकोत्तर महाविद्यालय शिवपुरी के खाते में अथवा ड्राफ्ट के द्वारा प्रदान किया जाना होगा। अपूर्ण निविदा को स्वीकार नहीं किया जावेगा । कार्य आदेश जारी होने के 15 दिवस के अन्दर कार्य पूर्ण करना होगा ।

संलग्नः– स्पेसीफिकेशन एवं **Price Schedule**

29/08/2022
(प्रो0 महेन्द्र कुमार)
प्रभारी प्राचार्य
शा0 स्नातकोत्तर महाविद्यालय,
शिवपुरी (म0प्र0)

पृ0क्रं0 2000 /2022 शिवपुरी दिनांक 29.08.22

प्रतिलिपिः–

1– आयुक्त, उच्च शिक्षा सतपुड़ा भवन भोपाल कृपया उपरोक्त विज्ञप्ति को विभागीय बेवसाईट पर अपलोड कराने का कष्ट करें।
2– प्रभारी प्राध्यापक , महाविद्यालय बेवसाईट पर कृपया उपरोक्त विज्ञप्ति को विभागीय बेवसाईट पर अपलोड कराने का कष्ट करें।
3– महाविद्यालय सूचना पटल पर इस आशय के साथ चस्पा कि संबंधित अपनी दरें प्रदान करें।

29/08/2022
(प्रो0 महेन्द्र कुमार)
प्रभारी प्राचार्य
शा0 स्नातकोत्तर महाविद्यालय,
शिवपुरी (म0प्र0)

Price Schedule

S.No.	Name Of Work	Quantity	Units	Estimated Rate in Rs. P.	Total Amount
1	2	3	4	5	6
1	Renovation Work of Govt. SMS P.G. College Shivpuri M.P.	1	Civil Work	5,70,073	5,70,073=00
					5,70,073=00

2	Rate	Above/Blow		Total Amount in Word	
				Total Amount in Number	

29/8/22
प्रो. पुनीत कुमार

10/9/2022
(Mahendra Kumar)
Principal
Govt. SMS P.G. College Shivpuri M.P.

DETAIL AND ABSTRACT ESTIMATE FOR RENOVATION WORK AT GOVT PG COLLEGE SHIVPURI

S. No.	SOR Ref.	Particular	Nos	L	W	D	Qty	Unit	Rate	Amount
1		Steel work in built up M.S. tubular section (round, square or rectangular hollow tubes etc.) trusses/frame work etc. including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.								
	10.14.1	Hot finished welded type tubes				Kg/per Sqm				
		Trush/ Purlin and Rafter for GS Sheet	1	15	7	7.25	761.3			
		Do for Cooler Shed	1	3	2.2	7.25	47.85			
		MS Compound Main gate No 2	1	4.35	2.4	40	417.6			
		Do	1	1.05	2.3	40	96.6			
		MS Main gate of College	1	1.8	2.7	40	194.4			
		MS gate For Cooridors	1	2.1	2.4	40	201.6			
		Total qty					1719.3	kg	108.00	185684
2		Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete upto any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.								
	12.1.2	0.80mm thick with zinc coating not less than 275gm/m²								
		Do for Cooler Shed	1	3	2.2		6.6			
		Do for Stage Shed	1	15	7.25		108.8			
							115.4	sqm	863.00	99547

26/8/22

Principal
Govt. P.G. College
Shivpuri (M.P.)

S. No.	SOR Ref.	Particular	Nos	L	W	D	Qty	Unit	Rate	Amount
3	SOR 10.5.2	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x5mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer.Using flats 30x6mm for diagonal braces and central cross piece.								
		Rooms	1	2.08	2.7		5.616			
		Cemister Cell 1	1	2.95	2.6		7.67			
		Library	1	2.5	2.35		5.875			
		Class Room	10	1.95	1.08		21.06			
		Total qty					40.22	SqM	2474	99507
4		Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :								
	21.1.2.2	For shutters of doors, windows and ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of Powder coated aluminium (minimum thickness of powder coating 50 micron)				Kg/per Sqm				
			5	1.7	1.5	10	127.5	Kg	345	43988

26/8/22

26/08/2022
Principal
Govt. P.G. College

S. No.	SOR Ref.	Particular	Nos	L	W	D	Qty	Unit	Rate	Amount
5	21.3.2	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item) :With float glass panes of 5.0 mm thickness (weight not less than 12.50 kg/sqm)								
			5	1.7		1.5	12.75	sqm	948.00	12087
6	27.8	Providing and fixing stainless steel English (Capital) and Hindi letters in standard pattern bellow type made with 1.20 mm thick stainless steel (ASI Grade- 304) Depth of letter shall not be less than 30mm and rate includes welding/soldering of joints polishing, buffing and fixing on the wall, plate and beam surface at any height with necessary nut and bolts/fastener wherever is required complete as per direction of Engineer-in-Charge.								
		College Name In Hindi	1	46	6		276			
		College Name In English	1	48	6		288			
							564	per letter per cm height	75.00	42300
		Total								483113
		Add GST 18%								86960
		Grand Total								570073

26/8/22

26/08/2022

Principal
Govt. P.G. College
Shivpuri (M.P.)